

Mayor Kirk D. Raffield

<u>Mayor Pro Tem</u> Dr. Folsom Proctor III

<u>City Manager</u> Brandon D. Douglas Council
John B. Foust, Jr.
Anne Sneve
Jim Looney
Brandon Hannah

<u>Deputy City Manager</u> Kim Goldener

RFP 2025 – 004 Stormwater Repairs at various locations Addendum No. 1 Issued 7-7-25

Question: Would the owner provide any specific culvert diameters and LF known for the repairs at Squaw Valley Road at Laurel Lane, and the repair at Stegall Drive east of Mary Street?

Answer: Please refer to exhibit "Stegall Drive" for information on the crossing of Stegall Drive east of Mary Street. The existing culverts crossing Squaw Valley Road at Laurel Lane are 48" diameter to the best of our knowledge.

Stegall Drive

Option 1: Replace Headwall, run +/- 150' of 42" Corrugated HDPE Pipe. Add two new catch basins. Compact and lay in 6" of 57 stone, remove and replace +/- 35 cy of asphalt, connect to existing storm pipe after sinkhole repaired.

Option 2: Run +/- 330' of 42"
Corrugated HDPE pipe; Add outlet structure in swale; Add two new catch basins. Compact and lay in 6" of 57 stone, remove and replace +/- 35 cy of asphalt, connect to existing storm pipe after sinkhole repaired.

